



City and County of Honolulu

JOHNSON
CONTROLS

Honolulu Hale

Energy Conservation Project

February 26, 2003

Slide 1 02/26/03

Facility Challenges

- ◆ Support of critical public service activities
- ◆ Aging physical plant equipment (25 yrs)
- ◆ Energy & operational inefficiencies
- ◆ Comfort & productivity issues
- ◆ Deferred maintenance
- ◆ Regulatory requirements
- ◆ Risk management
- ◆ Required system uptime

Slide 2 02/26/03

Honolulu Hale

530 South King Street Honolulu, Hawaii 96813

City & County of Honolulu's City Hall

Financial: \$ 3.1 M Cost \$ 125,000/yr. Savings

ECMS: High-Efficiency Centrifugal Chillers

220 kW Cogeneration System with 70 ton Absorption Chiller.

Induced Draft Cooling Tower

Primary/Secondary Chilled Water Loop with Variable-Speed pumping

T8, Elec. Ballasts, Compact Fluorescent lamps LED Exit signs, Occupancy sensors.

2-way Chilled Water Valve Change & Digital Temperature Control Retrofit.

Energy Management System


Electrical Cable Replacement



Slide 3 02/26/03

Proposed Energy Expenditure Savings

- ♦ **Energy Cost Reduction -** Guaranteed Annual Utility Cost Reduction of **41%**
- ♦ **Meet C&C of Honolulu Goals -** Significant Step towards Energy Reduction & Operational Flexibility Goals



Slide 4 02/26/03

Energy Conservation Measures

ECMs

- **ECM 1.1: Lighting Retrofit - Office Areas**
- **ECM 1.2: Lighting Retrofit/ Replacement - Public Areas**
- **ECM 2.1: Chiller Plant Replacement**
- **ECM 3.1: Energy Management System / AHU Valves and DDC Controllers**
- **ECM 4.1: Cogeneration System**

Slide 5 02/26/03

ECM 1.1 & 1.2 Lighting Retrofits

- ♦ **Office Lighting**
- ♦ **Architectural Lighting**



- T-8 Lamps w/Electronic Ballasts,
Compact Fluorescent Lamps
LED Exit Signs
Occupancy Sensors
- Install Correct Period Fixtures
- Improve Lighting levels and
Quality for Improved Work
Environment
- Reduce Lighting Maintenance
Costs

Slide 6 02/26/03

Use or disclosure of data contained on this sheet is subject to the restrictions on the title page of this document.

ECM 2.1 Central Plant Replacement

◆ Chillers & Cooling Tower

◆ Pumping Systems



- Replace Failing Equipment and meet Cooling Requirements
- Increase Operational Flexibility
 - High-Efficiency Chillers
- Induced Draft Cooling Tower
- Primary/Secondary Pumping
- New Electrical Cables to meet Building Code requirements

Slide 7 02/26/03

Use or disclosure of data contained on this sheet is subject to the restrictions on the title page of this document.

ECM 3.1 New AHU Valves & DDC Control

◆ New Energy Management System

◆ Digital Temperature Control




- Replace Failing Equipment and Improve Temperature Control for Productivity and Comfort Requirements
- Increase Operational Flexibility & Scheduling Abilities
- Quicker response to Hot & Cold Calls
 - New AHU Control Valves
- Digital Controllers tied to Energy Management Control System Network

Slide 8 02/26/03

ECM 4.1 Cogeneration System

- ◆ 220kW Cogenerator
- ◆ 55 ton Absorption Chiller



- Increase Operational Flexibility with flexible Cooling Capacity and Fuel Selection Choice
- Reduced Operational Costs
- Increase ability to operate facility during power outages
- Reduce “On-Peak” Electrical Demand to help defer future power plant & power line construction

Slide 9 mmpm


Estimated Utility Rebates

- ◆ **HECO Energy Solutions for Business Program**
 - Funding Approved through 2000.
 - Applied for a five year extension.
- ◆ **Schedule Meeting with HECO to Discuss Refining Rebate Levels**
 - Discussion about rebates (Custom versus Prescriptive)
 - Submit Applications
- ◆ **Estimated Rebates**
 - Prescriptive
 - Lighting = \$14,112
 - Motors = \$802
 - Chillers = \$18,750
 - Custom
 - Study = \$10,000
 - Lighting/HVAC = \$20,872

Slide 10 02/26/03


Use or disclosure of data contained on this sheet is subject to the restrictions on the title page of this document.

Electrical Load Profile - Sept. 99



Slide 11 02/26/03

Electrical Load Profile - Sept. 02



Slide 12 02/26/03

Hallway Lighting Before & After




Slide 13 02/26/03

Old & New Chillers



Slide 14 02/26/03

220 kW Cogeneration Unit




Slide 15 02/26/03

55 ton Absorption Chiller



Slide 16 02/26/03

Cogeneration Schematic



Slide 17 02/26/03

Courtyard Before & After



Slide 18 02/26/03

Mahalo

Are there any Questions?

Allyn Lee

C&C Honolulu Design & Construction Phone (808) 523-4106

650 South King Street, 9th fl.

email: alee2@co.honolulu.hi.us

Honolulu, Hawaii 96813